


Robust EL de Luxe

Production area

	Slab width														
	9600	10800	12000	13200	14400	15600	16800	18000	19200	20400	21600	22800	24000	25200	26400
Slab lenth	8 Rows	9 rows	10 rows	11 rows	12 rows	13 rows	14 rows	15 rows	16 rows	17 rows	18 rows	19 rows	20 rows	21 rows	22 rows
	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22
10000	178	200	222	244	267	289	311	333	356	378	400	422	444	467	489
12000	213	240	267	293	320	347	373	400	427	453	480	507	533	560	587
14000	249	280	311	342	373	404	436	467	498	529	560	591	622	653	684
16000	284	320	356	391	427	462	498	533	569	604	640	676	711	747	782
18000	320	360	400	440	480	520	560	600	640	680	720	760	800	840	880
20000	356	400	444	489	533	578	622	667	711	756	800	844	889	933	978
22000	391	440	489	538	587	636	684	733	782	831	880	929	978	1027	1076
24000	427	480	533	587	640	693	747	800	853	907	960	1013	1067	1120	1173
26000	462	520	578	636	693	751	809	867	924	982	1040	1098	1156	1213	1271
28000	498	560	622	684	747	809	871	933	996	1058	1120	1182	1244	1307	1369
30000	533	600	667	733	800	867	933	1000	1067	1133	1200	1267	1333	1400	1467

 = machine operating at full and more capacity

Therefore a slab of 18meters x 14.4 meters wil give you 480 drops

Stock bricks 480 x 15 =7200 per day

Maxi Bricks 480 x 11 =5280 per day

140 hollow blocks 480 x 6 =2880 per day